

DETAILED ESTIMATE OF FOR PAINTING WORK OF EXISTING N.I.T. BUILDING AT N.I.T. CAMPUS, RAIPUR (C.G.)

Name of work: Color washing, White washing, Painting, Distemping of the Institute Building from outside and all internal corridors of NIT, Raipur (CG)

NIT No. MBI/CON/662/127 DTD:13/12/2012

S.No.	I.No.	Particulars of items	Unit	Qty	DSR Rate	Non DSR Rate	Amount
1		Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete in all respect. (Ground Floor + First floor + Second floor)					
			sqm	29801.93	3.48		103710.72
2		Providing , applying and finishing walls with textured exterior paint of required shade .New work (Two or more coats applied @ 3.28 ltr/10 sqm) over and including base coat of water proofing cement paint applied @ 2.20kg/10 sqm complete in all respect.(Outer wall area of Ground floor+ first floor +Second Floor)					
			sqm	16844.06	104.72		1763909.96
		Outer side wall area					
3		Providing and applying three or more coats of acrylicemulsion paint of approved brand , manufacture and shade to give a smooth surface of new plastered surface over a coat of approved primer including the cost of preparing the surface with filling materials (putty) along with sand papering. Complete in all respect.(In Ground Floor + First Floor + second Floor).	Sqm	15416.24		119.68	1845015.60
Total							3712636
Rs.Thirty Seven Lacs Twelve Thousand Six Hundred and Thirty Six Only							